

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	4th main	1	355.00	4.50	0.05	79.88			
	5th main	1	235.00	4.50	0.05	52.88			
	9th cross	1	115.00	4.15	0.05	23.86			
	12th cross	1	92.00	4.75	0.05	21.85			
	Anganwadi road	1	249.00	4.40	0.05	54.78			
	20% Profile correction					557.29			
						111.46			
						111.46	Cum	6284.74	700487.69
14	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder a and filler, transporting the hot mix to work site, laying with a paver finisher with to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects as per specifications. using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr II (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-165,I No-21.22.6)								
	Basic rate	6683.00							
	Area weightage 6%	400.98							
	Total	7083.98							
	For Road								
	1st cross	1	151.00	4.80	0.04	28.99			
	2nd cross	1	148.00	4.00	0.04	23.68			
	3rd cross	1	140.00	4.20	0.04	23.52			
	4th cross	1	92.00	4.10	0.04	15.09			
	5th cross	1	89.00	6.10	0.04	21.72			
	6th cross	1	86.00	4.60	0.04	15.82			
	5th-6th connecting	1	35.00	5.00	0.04	7.00			
	7th cross	1	85.00	4.30	0.04	14.62			
	7th cross - LHS	1	71.00	5.00	0.04	14.20			
	2nd main	1	220.00	4.30	0.04	37.84			
	3rd main	1	215.00	6.60	0.04	56.76			
	4th main	1	355.00	4.50	0.04	63.90			
	5th main	1	235.00	4.50	0.04	42.30			
	9th cross	1	115.00	4.15	0.04	19.09			
	12th cross	1	92.00	4.75	0.04	17.48			
	Anganwadi road	1	249.00	4.40	0.04	43.82			
						445.83	Cum	7083.98	3158279.14
15	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflecting Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (P.No-185, I No-24.15)								
	Basic rate	512.00							
	Area weightage 6%	30.72							
	Total	542.72							
	For Road								
	1st cross	2.5	151.00	0.10		37.75			
	2nd cross	2.5	148.00	0.10		37.00			

Sl No	Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
	3rd cross	2.5	140.00	0.10		35.00			
	4th cross	2.5	92.00	0.10		23.00			
	5th cross	2.5	89.00	0.10		22.25			
	6th cross	2.5	86.00	0.10		21.50			
	5th-6th connecting	2.5	35.00	0.10		8.75			
	7th cross	2.5	85.00	0.10		21.25			
	7th cross - LHS	2.5	71.00	0.10		17.75			
	2nd main	2.5	220.00	0.10		55.00			
	3rd main	2.5	215.00	0.10		53.75			
	4th main	2.5	355.00	0.10		88.75			
	5th main	2.5	235.00	0.10		58.75			
	9th cross	2.5	115.00	0.10		28.75			
	12th cross	2.5	92.00	0.10		23.00			
	Anganwadi road	2.5	249.00	0.10		62.25			
						594.50	Sqm	542.72	322647.04
	Total Construction Cost								9458662.26
	DPR Charges								91,000.00
	PMC Charges								100000.00
	Sub Total								9649662.26
	Miscellaneous & Rounding off								350337.74
	GRAND TOTAL								10000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR, Bangalore circle for year 2016-2017 and Data Rates

Hundresh
Assistant Engineer,
Yelahanka Project Division,
BBMP Bangalore

Chilab
Asst. Executive Engineer
Yelahanka Project Division,
BBMP Bangalore
Bangalore

H.V. J
Executive Engineer
Yelahanka Project Division,
BBMP Bangalore

BRUHAT BANGALORE MAHANAGARA PALIKE

Project: Improvements to Roads and Drains at Kattigenahalli Kuvempunagara Cross Roads in Ward No 05 Byatarayanapura Sub division

Est Cost: =40.0Lakh									
Sl. No.	Description of work	Unit	No.	Length m	Breadth m	Depth m	Quantity	Rate in	Amount in
								Rs.	Rs.
1	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&I WTD SR 2016-17)								
	Desilt	Cum							
	Kuvempunagara								
	6th Cross LHS		2	65.00	0.50	0.45	29.25		
	7th Cross LHS		2	75.00	0.50	0.45	33.75		
	8th Cross LHS		2	75.00	0.50	0.45	33.75		
	9th Cross LHS		2	60.00	0.50	0.45	27.00		
	6th Cross RHS		2	95.00	0.50	0.45	42.75		
	7th Cross RHS		2	85.00	0.50	0.45	38.25		
	8th Cross RHS		2	80.00	0.50	0.45	36.00		
	9th Cross RHS		2	90.00	0.50	0.45	40.50		
	Kuvempunagara								
	Main Road		2	160.00	0.50	0.45	72.00		
	cross Road 1		2	55.00	0.50	0.45	24.75	186.92	70655.76
2	KSRRB M300-14. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications. MORTH Specification No.301 (P.No.143, I.No.19.14 of PW,P&I WTD S.R 2016-17)								
	Road Portion	Cum							
	Kuvempunagara								
	6th Cross LHS		1	65.00	4.90	0.23	73.26		
	7th Cross LHS		1	75.00	4.80	0.23	82.80		
	8th Cross LHS		1	75.00	4.90	0.23	84.53		
	9th Cross LHS		1	60.00	4.40	0.23	60.72		
	6th Cross RHS		1	95.00	4.40	0.23	96.14		
	7th Cross RHS		1	85.00	5.30	0.23	103.62		
	8th Cross RHS		1	80.00	4.90	0.23	90.16		
	9th Cross RHS		1	90.00	3.90	0.23	80.73		
	Kuvempunagara								
	Main Road		1	160.00	5.50	0.23	202.40		
	cross Road 1		1	55.00	4.60	0.23	58.19		
	Cross Roads		3	40.00	4.90	0.23	135.24	155.16	165675.97

[illegible]



BRUHAT BANGALORE MAHANAGARA PALIKE

**Project: Improvements to Roads and Drains at Dwarakanagar Srirama Temple Road In Ward No 05
Byatarayanapura Sub division**

Sl. No.	Description of work	Unit	No.	Length m	Breadth m	Depth m	Quantity	Est Cost: = 30.0 Lakh Rate In Rs.	Amount in Rs.
1	Removing B.S Slab of Drain and Slacking (P.No.25, I.No.5.32 of PW, P&IWD SR 2016-17)								
	Dwarakanagar (bagalur Mn Rd to Netaji Rd)								
	BS Slab Drain	Sqm							
	LHS								
	Ch 0 - 240		1	240.00	1.80	--	432.00		
	RHS								
	Ch 0 - 365		1	365.00	1.80	--	657.00		
	consider 30% missing / damaged						1089.00		
							-326.70		
							762.30		
							762.30	65.72	50098.36
2	KSRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWD SR 2016-17)								
	Dwarakanagar (bagalur Mn Rd to Netaji Rd)	Cum							
	Desilling								
	LHS								
	Ch 0 - 240		1	240	0.40	0.50	48.00		
	RHS								
	Ch 0 - 365		1	365	0.40	0.50	73.00		
	New								
	Culverts		2	5.50	1.60	1.20	21.12		
							142.12	186.92	26565.07
3	Refixing Stone Slabs of Drains and pointing in C M (1:3) (P.No.25, I.No.5.33 of PW, P&IWD SR 2016-17)								
	same as Qty 1	Sqm	--	--	--	--	762.30	80.56	61410.89
4	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWD SR 2016-17)								
	New Drain	Sqm							
	same as Qty 1						326.70	665.68	217477.66
5	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.2 of PW, P&IWD S.R 2016-17)								
	Dwarakanagar (bagalur Mn Rd to Netaji Cum Flagging Course / Raising of BS Drain								
	LHS								
	Ch 0 - 240		2	240.00	0.20	0.10	9.60		
	RHS								
	Ch 0 - 365		2	365.00	0.20	0.10	14.60		
	New								
	Culverts		2.00	5.50	1.60	0.15	2.64		
							26.84	5348.76	143560.72